

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-22,260-0000

LEASE NAME G. Rugg

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 9 TWP. 34 RGE. 10 (E) or (W)

COUNTY Barber

Date Well Completed 10-09-89

Plugging Commenced 10-09-89

Plugging Completed 10-10-89

LEASE OPERATOR Sullivan & Company

ADDRESS Suite 1700, 320 S. Boston Tulsa, OK 74103

PHONE# (918) 584-4288 OPERATORS LICENSE NO. 3384

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-06-89 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, Is well log attached? yes

Producing Formation Dry P & A Depth to Top ---- Bottom --- T.D. 4270'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Tonkawa	SW	0'	316'	8 5/8"	316'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 600' w/50 sacks 60/40 pozmix 6% gel thru drill pipe  
Next Plug: @ 330' w/40 " " " " " " "  
Next Plug: @ 40' w/ 10 " " " " " " "  
15 sacks in Rat Hole 10 in mouse hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. DEC586A

Address P.O. Box 877 Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sullivan & Company **OCT 30 1989**

STATE OF Kansas COUNTY OF Barton, ss. CONSERVATION DIVISION  
Wichita, Kansas

Ervin Neighbors (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 23rd day of October, 19 89

Sally R. Byers  
Notary Public  
My Commission Expires: December 6, 1992

RECEIVED

OCT 27 1989

DRILLER'S WELL LOG

DATE COMMENCED: October 3, 1989  
DATE COMPLETED: October 10, 1989

Sullivan & Company  
G. RUGG #1 SULLIVAN and COMPANY  
C S/2 S/2 NE  
Sec. 9, T34S, R10 W  
Barber County, Ks.

ELEVATION: 1394 K.B.

0 - 650' Surface Soil, Red Bed, Shale  
650 - 3115' Shale  
3115 - 3590' Lime & Shale  
3590 - 3654' Lime  
3654 - 3770' Lime & Shale  
3770 - 4270' Shale & Lime  
4270' RTD

Surface Pipe: Set  
8-5/8", 23# pipe @316'  
w/200 sacks 60/40 pozmix  
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

RECEIVED  
STATE CONSERVATION COMMISSION

OCT 30 1989

CONSERVATION DIVISION  
Wichita, Kansas

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*

Subscribed and sworn to before me this 23rd day of October 1989.

 SALLY R. BYERS  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 12/16/92

*Sally R. Byers*  
Notary Public