

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 007-20993-0000

LEASE NAME Davis

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER Q-3

         Ft. from S Section Line

         Ft. from E Section Line

LEASE OPERATOR Clark Exploration Co.

SEC. 36 TWP. 34S RGE. 15 ~~XXXX~~(W)

ADDRESS 75 Falcon Hills Dr., Highland Ranch, CO 80126

COUNTY Barber

PHONE#(303) 797-7500 OPERATORS LICENSE NO. 9026

Date Well Completed         

Character of Well Csg. leak

Plugging Commenced 6/24/97

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/27/97

The plugging proposal was approved on 6/24/97 (date)

by Steve Piefer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4620 Bottom 4630 T.D. 4871

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4	286	None
				8 5/8	1090	None
				5 1/2	4912	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from          feet to          feet each section. Tally and run tubing to 610, tight spot and try to load hole, pull tubing and push 5 1/2 wiper plug to 600, load hole and circulate with 300sx cement, well went on vacuum, let cement set up, tag cement at 500, load 5 1/2 and circulate cement to surface, pressure test to 300lbs. pump 100sxs down 8 5/8, try to pump 10 3/4, but was already cemented, 60/40 6% jel.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Clark Exploration Co.

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.



(Signature) [Signature]

(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 7 day of July, 1997

[Signature]  
Notary Public

My Commission Expires: 10/14/98