


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 23 Twp. 34 Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NE NW
Lease Owner Raymond Oil Co., Inc.
Lease Name Davis Ranch I #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12/20/77 19
Plugging completed 3/17/78 19
Reason for abandonment of well or producing formation
depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4779
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
MAR 21 1978 3-21-1978				8-5/8	879	none
CONSERVATION DIVISION Wichita, Kansas				5 1/2"	4777	1291'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Tried to kill well, pumped 40 sacks cement on bottom. Checked hole, found top of cement at 3800', got weight caught at 3100', worked weight loose. Tried to load hole with water, pumped 160 bbls. Casing would not hold water. Checked hole, got down to 630', bailer would not go down. Shot pipe at 2810', pipe parted, pulled 20 joints. Set rock bridge at 420' and ran 2 sacks cement. Ran 6 1/2 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Walter Voth*
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of Jan., 1978



My commission expires _____

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- CHAMPLIN OIL & REFINING CO.
Farm- Davis Ranch "I" No. 1

SEC. 23 T. 34 R. 15W
NW NE NW

Total Depth. 4779'
Comm. 6-2-61 Comp. 6-23-61
Shot or Treated.
Contractor. Hw30, Inc.
Issued. 10-7-61

County Barber
KANSAS



Elevation. 1595' DP

Production. 2,800,000 CFG

CASING:

13 3/8" 201' cem w/225 sx.
8 5/8" 879.45' cem w/100 sx.
5 1/2" 4777.9' cem w/50 sx.

Figures indicate Bottom of Formations.

top soil	120
red bed & shells	770
red bed	883
Reaming to 12 1/4"	201 to 880
shale & shells	1880
lime & shale	2080
lime	2185
lime & shale	2840
shale & shells	2925
shale & lime	3040
lime & shale	3095
shale & shells	3195
shale & lime	3350
shale & shells	3430
shale & lime	3695
shale & shells	3795
shale & lime	3960
lime & shale	4130
shale & lime	4140
lime	4162
lime & shale	4215
lime	4260
lime & shale	4290
lime	4778 RFD
lime	4779
Total Depth	

TOPS: ELECTRIC

Heebner	3930
Toronto	3943
Douglas	3962
Lansing-Kansas City	4138
Base Kansas City	4629
Marmaton	4641
Cherokee	4740
Mississippian	4751

DST #1 4738-4778', op 2 hrs, gas to surf.
in 4 mins. Gauged 240 MCFG immediately
206 MCFG/10 min, 206 MCFG/20 min.
196 MCFG/30 min & stabilized to end of
test.

Perforated 4754-4766' w/2 shots per foot.
Treated: 500 gal. mud acid at 700#.

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1977
CONSERVATION DIVISION
Wichita, Kansas