

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-30404-0001

LEASE NAME Graves

WELL NUMBER 2A SWD

SPOT LOCATION C E/2 NW NW

SEC. 19 TWP. 34S RGE. 13W (E) or (W)

COUNTY Barber

Date Well Completed _____

Plugging Commenced 2-21-86

Plugging Completed 2-28-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oneak Exploration Company

ADDRESS P.O. Box 871 100 W. 5th St. Tulsa, Ok. 74102

PHONE # (918) 588-7700 OPERATORS LICENSE NO. 4548

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4823'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	350'	none
				4-1/2"	4800'	3289'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4100' and ran 4 sacks cement. Shot casing @3820', 3600', 3430' and 3289'. Layed down a total of 102 joints (3289') of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull and 150 cement. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address P.O. Box 347 Chase, Kansas 67530

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as stated that the same are true and correct, so help me God.

3-5-1986

MAR 5 1986 (Signature) R. Darrell Kelso

CONSERVATION DIVISION
Wichita, Kansas (Address) P.O. Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 1986

Jimm Hoover
Notary Public

My Commission expires:



SCHLUMBERGER WELL SURVEYING CORPORATION

HOUSTON, TEXAS



Laterolog

WITH GAMMA RAY

COUNTY <u>BARBER</u> FIELD or LOCATION <u>SEC 19-34S-13W</u> WELL <u>GRAVES NO.</u> COMPANY <u>MOBIL OIL COMPANY</u>	COMPANY <u>MOBIL OIL COMPANY</u>	Other Surveys
	WELL <u>GRAVES NO. 1</u>	Location of Well
	FIELD <u>AETNA MISS. GAS POOL</u>	55 990' F#L
	LOCATION <u>SEC 19-34S-13W</u> <u>C E/2 NW/4 NW</u> PROPERTY OF	DIVISION <u>30752</u>
COUNTY <u>BARBER</u>	COUNTY <u>BARBER</u>	Elevation: K.B.: <u>1646</u> D.F.: <u>1643</u> or G.L.: <u>1637</u>
STATE <u>KANSAS</u>	<u>K. G. S. LIBRARY</u> 540 Petroleum Bldg. Wichita, Kansas 67201	

Log Depths Measured From KB 9 Ft. above GL

RUN No.	<u>ONE</u>							
Date	<u>1-10-61</u>							
First Reading	<u>4823</u>							
Last Reading	<u>345</u>							
Feet Measured	<u>4478</u>							
Csg. Schlum.	<u>345</u>							
Csg. Driller	<u>345</u>							
Depth Reached	<u>4826</u>							
Bottom Driller	<u>4825</u>							
Mud Nat.	<u>Salt Emulsion</u>							
Dens. Visc.	<u>9.6</u>	<u>54</u>						
Mud Resist.	<u>200</u>	<u>68</u>	F					F
Res. BHT	<u>125</u>	<u>15</u>	F					F
pH	<u>6.8</u>		F					F
Wtr. Loss	<u>10</u>	CC 30 min			CC 30 min			CC 30 min
Rmf (M)	<u>120</u>	<u>72</u>	F					F
Rmc			F					F
Bit Size	<u>7 7/8</u>							
Laterolog 3	<u>6"</u>	<u>3'</u>						
Laterolog 7								
Opr. Rig Time	<u>1 1/2 Hrs</u>							
Truck No.	<u>2536-Pratt</u>							
Recorded By	<u>Morgan</u>							
Witness	<u>Mitchell</u>							

JAN 31 1966

CONSERVATION DIVISION

FOLD HERE

