


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 25 Twp. 29^S Rge. 12W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SE NW
Lease Owner F. G. Holl
Lease Name Turner "B" #1-25 Well No. 1-25
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed October 26, 1981
Application for plugging filed October 26, 1981
Application for plugging approved October 26, 1981
Plugging commenced 4:00 PM October 26, 1981
Plugging completed 5:00 PM October 26, 1981
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2840'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	306'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 620' with 60 sacks 50/50 Pozmix
with 4% gel and 3% cc thru open ended drill pipe;
heavy mud to 280' with 40 sacks thru open ended
drill pipe; 1/2 sack hulls and Howco plug with
solid bridge at 40', 10 sacks to surface and
10 sacks in rathole thru 2" pipe.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
STERLING DRILLING COMPANY
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October 19 81.

My commission expires



RECEIVED
AGNES D. WURST
Notary Public.

NOV 6 1981
11-06-81
CONSERVATION DIVISION
Wichita Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - TURNER "B" #1-25
Located: C SE NW, Section 25-28S-12W, Pratt County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 22, 1981
COMPLETED: October 26, 1981

TOTAL DEPTH: 2840'

<u>LOG</u>	<u>CASING RECORD</u>
0 ~ 130 Sand	Ran 7 joints 8 5/8", 23# new surface casing. 295.68' pipe set at 306' K.B.
130 ~ 310 Shale	Cemented with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 9:15 PM, 10-22-81, by Halliburton.
310 ~ 550 Shale and Shells	
550 ~ 1520 Shale	
1520 ~ 1755 Shale and Lime Stringers	
1755 ~ 2450 Lime and Shale	
2450 ~ 2650 Lime	
2650 ~ 2810 Lime and Shale	
2810 ~ 2840 Lime	Plugged.

Deviation Surveys: 2° at 1900'
2° at 2810'