

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,732-00-46

LEASE NAME Huitt

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 1 SW SE NE
TWP. 28S RGE. 15 KK or (W)

LEASE OPERATOR Knighton Oil Company, Inc.

COUNTY Pratt

ADDRESS 710 Petroleum Bldg. Wichita, Ks. 67202

Date Well Completed

PHONE# (316) 264-7918 OPERATORS LICENSE NO. 5010

Character of Well Oil

Plugging Commenced 4-20-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-25-89

The plugging proposal was approved on April 18, 1989 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4676

Perfs: 4531-37; 4507-17; 4528-38 PBTD 4600
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR OTHER RECORDS

CASING RECORD

Format	Content	From	To	Size	Put In	Pulled out
		0	411	8 5/8	411	0
			4600	4 1/2	4600'	2135' 53' jts.

Describe in concise manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Moved to location, dumped 100 gallons of sand down well, and water. Sand to 4450', ran dump bailer with 4 sx. cement. / Shot pipe off at 2135', and pulled out 53 jts. of casing.
4-25-89: BI Titan pumped 400# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls.
8 5/8 plug, 100 sx. cement, 60-40 poz mix, 6% gel. Max 450#. STP 200#.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company


STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of plugging contractor)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P.O. Box 847-Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 89

Dorothy M. Furgason
Notary Public

My Commission Expires: February 6, 1993