


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County, Sec. 36 Twp. 28 Rge. (E) 14W(W)
Location as "NE/CNW%SW%" or footage from lines SW SW SE
Lease Owner Lario Oil & Gas Co.
Lease Name Moore Well No. 1
Office Address 301 S. Market, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed May 28 1954
Application for plugging filed March 15 1961
Application for plugging approved March 20 1961
Plugging commenced April 12 1961
Plugging completed April 19 1961
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production March 31 1961
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Simpson & K.C. Depth to top _____ Bottom _____ Total Depth of Well 4663 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	366	Cemented
				5 1/2	4669	
				Set @ 4660'		3589'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand from T.D. to 4200'. 4 sacks cement to 4175'. Mud to 265'. 10' rock bridge 20 sacks cement to 190'. Mud to 35'. Rock bridge and 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1961
5-4-61
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leo Ross (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo Ross
301 S. Market, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 61

My commission expires July 21, 1962

Frances Leslie
Notary Public.

cc. Sinclair Oil & Gas Company
P. O. Box 521
Tulsa 2, Oklahoma
Att: Mr. C. S. Rose, Div. Prod. Supt.

LANIO OIL & GAS CO. ET AL
 Earl Moore No. 1
 SW SW SE Sec. 36-28N-14W
 Pratt County, Kansas

Drilling Commenced: 5-5-54
 Drilling Completed: 5-28-54
 Well Completed: 6-2-54
 Drilling Contractor: Sterling Drilling Co.
 T.D. (Drillers) 4661'
 T.D. (Schlumberger) 4663'

Casing Record:
 8 5/8" 366' O.A. Set @ 360'
 Cem. w/ 300 lbs. Pozmix,
 150# Floccle & 6 sacks cal.
 chloride
 5 1/2" 4669' O.A. Set @ 4660' w/
 200 sacks cement

Initial Pot. : 1258 oil/ 24 hrs.
 from Simpson (6-16-54)

<u>Formation</u>	<u>Depth</u>
Shale & sand	225
Sand & red bed	360
Red bed & shale	635
Sand & red bed	805
Anhydrite	825
Red bed, shale & shells	1160
Shale & shells	1450
Shale	1940
Lime	2125
Lime & shale	2275
Lime	2375
Lime & shale	2595
Lime	2670
Lime & shale	3185
Lime	3240
Lime & shale	3340
Lime	3755
Lime & shale	3810
Sand & shale	3955
Lime & shale	3972
Lime	4440
Lime & conglomerate	4475
Viola chert	4500
Lime	4537
Simpson	4621
Lime	4661
Schlumberger T.D.	4663

<u>Geological Top:</u>	1982 D.F.	1984 R.B.
Elev.		
Topoka	3173	-1189
Heebner	3773	-1789
Toronto	3791	-1807
Base Broad	3813	-1829
Lansing-K.U.	3963	-1979
Conglomerate	4454	-2470
Viola	4480	-2496
Simpson	4514	-2530
Arbuckle	4621	-2637
Schlumberger T.D.	4663	-2679

Perf. Welox 4512-18 and 4520-34.
 Acidized 500 gals. mud acid and
 500 gals. wash by Dowell
 Sandfraced w/ 8000#
 Perf. R.C. 4223-4227 w/ 6 shots per
 foot (Welox)
 Acidized 250 gal. XF32 and 750 gals.
 etching acid
 Acidized 2500 gals. Jel 1100

(Dual Completed)

I hereby certify that this is a true and
 correct log of the above mentioned well.

[Signature]

STATE OF KANSAS)
 COUNTY OF SEDGWICK } SS

Subscribed and sworn to before me, a
 notary public, in and for said County and
 State this 22nd day of June, 1954.

[Signature]
 Notary Public

My Commission expires July 21, 1954.

RECEIVED
 STATE CORPORATION COMMISSION

MAR 16 1961

CONSERVATION DIVISION
 Wichita, Kansas