


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County, Sec. 36 Twp. 28S Rge. 14 (E) (W)  
Location as "NE/CNW4SW4" or footage from lines C NW NW NE  
Lease Owner Phillips Petroleum Company  
Lease Name Pratt "A" Well No. 1  
Office Address Box 779 - Great Bend, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 12, 1955  
Application for plugging filed December 13, 1955  
Application for plugging approved December 14, 1955  
Plugging commenced December 23, 1955  
Plugging completed December 31, 1955  
Reason for abandonment of well or-producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives  
Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4595 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	3756		9 5/8"	357.33	None
Toronto	Dry	3776		7"	4597.68	3167'
Douglas	Dry	3797				
Brown Lime	Dry	3940				
LKC	Dry	3963				
Drum	Dry	4121				
Base LKC	4320	4320				
Marmaton	Dry	4336				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mississippian	Dry	4422'				
Viola	Dry	4457'				
Simpson Shale	Dry	4490				
Simpson Sandstone	Dry	4503				
Arbuckle	Dry	4586	4595'			

Drilled well to original total depth of 4595'. Top of cement when setting casing was at 4535' - did not drill out. Set Baker bridge plug at 4175'. Set bridge plug at 4045'. Plugged back with sand to 3760', dumped 5 sx. cement to 3725'. Mudded hole from 3725' to 225'. Rock bridge from 225' to 215'; 20 sx. cement 215' to 165'; Mudded 165' to 25'; 10' rock bridge 25' to 15'. Dumped 10 sx. cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, SS.  
A. J. Willis (employee of owner) of Phillips Petroleum Company of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 779 - Great Bend, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of January, 1956

My commission expires 11/18/57

[Signature] Notary Public.

24-7368-5 3-53-20M

**PLUGGING**  
FILE SEC 36 T 28 R 14 W  
BOOK PAGE 23 LINE 43

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 5 - 1956  
1-5-56  
CONSERVATION DIVISION

Phillips Petroleum Company

EXPLORATION RECORD

Pratt "A" #1 - 330' from North and 2315' from East Lines, NE/4

Section 36-28S-14W, Pratt County, Kansas - Dry Hole

Lease Pratt "A"

Well 1

Formation Name	Top	Base	Remarks
Clay and sand	0	202	
Sand and redbed	202	359	
Shale and shells	359	465	
Redbed and shale	465	734	
Sand and shale	734	1300	
Shale, shells and salt	1300	1736	
Shale and shells	1736	2001	
Lime	2001	2437	
Lime and shale	2437	3670	
Lime	3670	3864	
Lime and shale	3864	3970	
Lime	3970	4394	
Lime and chert	4394	4510	
Sand, shale and lime	4510	4548	
Lime and shale	4548	4588	
Lime	4588	4595	

FORMATION TOPS: (Sample)

Not penetrated at 4595' TD.

Hoebner	3756
Toronto	3776
Douglas	3797
Brown Limestone	3940
Lansing-Kansas City	3969
Orua	4121
Base-Kansas City	4320
Harmston	4336
Mississippian	4422
Viola	4457
Simpson Shale	4490
Simpson Sandstone	4503
Arbuckle	4586
Rotary Total Depth	4595
Cable Tool TD	PD 4045

Form 883 3-53

Well Plugged and abandoned.

**PLUGGING**  
 FILE SEC 36-28-14W  
 BOOK PAGE 23 LINE 43

**RECEIVED**  
 STATE CORPORATION COMMISSION

JAN 5 - 1956

CONSERVATION DIVISION  
 Wichita, Kansas