

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-151-19091-00-A1

API NUMBER 9/13/68

LEASE NAME Beard

WELL NUMBER 1

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 36 TWP. 28S RGE. 14W (E) or (W)

COUNTY Pratt

Date Well Completed 9/13/68

Plugging Commenced 10/01/91

Plugging Completed 10/02/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Knighton Oil Company, Inc.

710 Petroleum Bldg.
ADDRESS Wichita, Kansas 67202

PHONE# (316) 264-7918 OPERATORS LICENSE NO. 5010

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 23, 1991 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? NO If not, Is well log attached? Yes

Producing Formation N/A Depth to Top N/A Bottom N/A T.D. 1050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	434'	9 5/8"	434'	None
		Surface	830'	6"	830'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 50 sacks std cement 3% c.c. and squeezed from 815' to 1050 ft. pressured to 150 psi and shut in overnight. Plug held @300 psi. Backed tubing off at packer set at 802 feet and pumped 75 sx. pozmix, 2% gel and filled casing to surface. Pumped 75sx. pozmix between surface pipe and 6" casing & shut in. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Bowers Drilling Co., Inc. License No. 5435

P.O. Box 241
Address Medicine Lodge, Kansas 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Earl M. Knighton, Jr.

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Earl M. Knighton, Jr.
(Address) 710 Petroleum Bldg. Wichita, KS

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1991

Sarah A. Simon

Notary Public

My Commission Expires: 12/11/93

Sarah A. Simon

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company-ROLAND S. BOND

Farm- Beard

No. 1.

SEC. 36

T. 28

R. 14W

NW SE NW

Total Depth. 4600'

Comm. 11-17-59

Comp. 11-27-59


Shot or Treated.

Contractor. S & S Drilling

Issued. 2-6-60

County Pratt

KANSAS



Elevation. 1994 KB

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	235
red bed & shale	840
shale & sholls	1345
salt	1650
shale & lime	1970
lime & shale	2490
shale & lime	2545
lime & shale	2680
shale & lime	3200
lime & shale	3822
shale	3850
shale & sand	3940
lime & shale	4095
lime	4150
lime & shale	4517
sand	4595
lime arbuckle	4600
Total Depth	

TOPS

Heebner	3773
Dodge	3796
Douglas	3824
Brown Lime	3956
Lansing	3970
Base Kansas City	4326
Marmaton	4342
Cherok ee	4405
Viola	4448
Simpson Shale	4509
Simpson Dolomite	4512
Simpson Sand	4522
Arbuckle	4595

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 18 1991

CONSERVATION DIVISION
WICHITA, KS

K. G. S. LIBRARY