


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 36 Twp. 28S Rge. (E) 14 (W)

Location as "NE/CNWSW" or footage from lines. W/2 W/2 NE
Lease Owner. Tilco, et al
Lease Name. Beard Well No. 1
Office Address. 200 Sutton Place - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-11 1969
Application for plugging filed 7-11 1969
Application for plugging approved 7-11 1969
Plugging commenced 7-11 1969
Plugging completed 7-11 1969
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				331'	8 5/8"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 1/2 sack hulls @ 250' 25 sacks cement
Mud to 40' 1/2 sack hulls 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1969 7-24-69
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor. Leben Drilling, Inc.
Address. Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address) _____

Sworn to before me this 22nd day of July, 1969
Ulanda Nichols
Notary Public.



DRILLER'S LOG

COMPANY Tilco, et al
 CONTRACTOR LEBEN DRILLING, INC.
 FARM BEARD #1
 LOGATION W/2 W/2 NE SECTION 36-28S-14W
 PRATT COUNTY, KANSAS
 COMMENCED 6-29-69
 COMPLETED 7-11-69

0	190	Clay, Sand
190	232	Sand
232	824	Red Bed
824	844	Anhydrite
844	1678	Shale, Shells
1678	1927	Shale
1927	2030	Shale with Lime Streaks
2030	2270	Lime
2270	2505	Lime, Shale
2505	2560	Shale, Lime
2560	2705	Shale
2705	3040	Shale, Lime Streaks
3040	3130	Shale, Lime
3130	3235	Shale, Lime Streaks
3235	3775	Shale, Lime
3775	3910	Lime, Shale Streaks
3910	4450	Lime
4450	4478	Lime, Chert, Viola
4478	4620	Lime
	<u>4620</u>	<u>RTD - D. & A.</u>

8 5/8" 20# new surface casing set @ 331' cemented with 325 sacks Common cement 2% cc


I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Beard #1 Well, located W/2 W/2 NE of Section 36, Township 28 South, Range 14 West, Pratt County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 24 1969
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Pratt County, Kansas, this 22nd day of July, 1969.



Ulanda Nichols
 Ulanda Nichols