

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Kiowa County. Sec. 23 Twp. 29S Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines C SE/4 SE/4
Lease Owner Stickle Drilling Company
Lease Name Black Well No. 1
Office Address 1027 Union Center, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 18 September 19 59
Application for plugging filed 18 September 19 59
Application for plugging approved 18 September 19 59
Plugging commenced 18 September 19 59
Plugging completed 18 September 19 59
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr.
Producing formation None Depth to top Bottom Total Depth of Well 5230 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	surface	150	8-5/8	570'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy rotary mud was placed to 400 feet.
1/2 sack of hulls, a wooden plug and 30 sacks of cement were placed at 400 feet.
Heavy rotary mud was then placed to 35 feet.
1/2 sack of hulls, a wooden plug and 20 sacks of cement were placed at 35 feet.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stickle Drilling Company
Address 1027 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clifford M. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clifford M. Smith
1027 Union Center, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23 day of September 19 59
Charley V. Shank, Notary Public.

My commission expires 17 February 1962

PLUGGING
File Sec. 23 T 29 R 20W
Book Page 4 Line 30

Stickle Drilling Company
Wichita, Kansas

Tulsa, Oklahoma
September 21, 1959

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: September 2, 1959
Drilling Completed: September 18, 1959

No. 1 Black (189) C SE
SE 23-29S-20W, Kiowa County
Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation:

Surface	0
Clay & Gyp	90
Shale & Shells	830
Shale, Shells & Salt	1020
Red Bed Shale & Shells	1530
Shale & Shells	2290
Lime & Shale	2665
Lime	3165
Lime & Shale	3385
Shale & Lime	4150
Lime & Shale	4512
Lime	5098
Lime & Shale	5157
Lime	5230 TD

I, Fred E. Stickle hereby certify the above to be a true and complete
Drillers Log of Stickle Drilling Company Etal No. 1 C SE SE 23-29S-20W
Kiowa County, Kansas.

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1959

Fred E. Stickle
Fred E. Stickle

CONSERVATION DIVISION
Wichita, Kansas

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

PLUGGING

File Sec. 23 T 29 R 20W

Book Page 4 Line 30