

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Haskell County. Sec. 28 Twp. 29 Rge. 34 (X) (W)

Location as "NE/CNW%SW%" or footage from lines NW/SE

Lease Owner Ashland Oil & Refining Company

Lease Name Koenig Well No. 4

Office Address P.O. Box 127 - Satanta, Kansas 67870

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 19, 1961 1961

Application for plugging filed May 26, 1966 1966

Application for plugging approved June 30, 1966 1966


Plugging commenced 7-11 1966

Plugging completed 7-12 1966

Reason for abandonment of well or producing formation Well will no longer produce commercially.

If a producing well is abandoned, date of last production September 23, 1964

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Edd Eves

Producing formation Morrow Depth to top 5243 Bottom 5307 Total Depth of Well 5501 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1827	None
				5 1/2	5498	1980

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mix 20 sacks cement to plug off perforations at 5243 feet.
Stop plug at 5050 feet. Shoot pipe off at 1980 feet. Pump
35 sacks cement at 700 to 600 feet. Put 15 sacks cement at
45 feet to 0 feet.
Mud laden fluid between all plugs.

RECEIVED
STATE CORPORATION COMMISSION
JUL 21 1966
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor Sargents Casing Pulling Service
Address Box 506 Liberal, Kansas

STATE OF Kansas, COUNTY OF Haskell, ss.

James H. Ipson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James H. Ipson
P.O. Box 127 - Satanta, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 1966

My commission expires October 1, 1966
H. J. Hughes Notary Public.

Suot.	<input type="checkbox"/>
Eng.	<input checked="" type="checkbox"/>
Geol.	<input type="checkbox"/>
Prod.	<input checked="" type="checkbox"/>
Land	<input type="checkbox"/>
Scout	<input type="checkbox"/>
Denver	<input type="checkbox"/>
Gen. Off.	<input type="checkbox"/>
File	<input checked="" type="checkbox"/>

STARTED: April 22, 1961

COMPLETED: May 9, 1961

L O G

Surface, Sand	0'	650'	Syfo @ 150' 1/4°
Sand, Red Bed & Gyp	650'	1125'	
Red Bed & Gyp	1125'	1782'	Syfo @ 1255' 1/2°
Anhydrite	1782'	1828'	8 5/8" csg. @ 1827' w/750 Sx Common & 4% Gel
Anhydrite & Lime	1828'	2400'	
Lime	2400'	2896'	Syfo @ 2800' 1°
Lime & Chalk	2896'	3302'	
Lime	3302'	3504'	
Lime & Shale	3504'	3838'	
Lime	3838'	3965'	
Lime & Shale	3965'	4078'	
Lime, Shale, & Sand	4078'	4122'	
Lime & Shale	4122'	4311'	
Lime	4311'	4758'	
Lime & Blue Shale	4758'	4849'	
Lime & Shale	4849'	4905'	
Lime	4905'	5286'	Syfo @ 5160' 2°
Lime & Shale	5286'	5415'	
Lime	5415'	5424'	
Sand & Lime	5424'	5490'	
Lime	5490'	5500'	5 1/2" csg. @ 5498' w/ (1st stage) T. D. 325 cu. ft. Posmix & 50 cu. ft. posmix w/ latex (2nd stage) @ 2881

RECEIVED
 STATE CORPORATION COMMISSION

JUN 30 1966

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

I, R. M. Green, do hereby certify that the above is a true and accurate log of the Charles Koenig Well No. 4, located in NW SE of Sec. 28-29S-34W, Haskell County, Kansas.

R. M. Green
 Secretary-Treasurer

Subscribed and sworn to before me this 17th day of May, 1961.

Robert E. Gabe
 Notary Public

My Commission Expires: June 14, 1962.