

15-151-20922-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD SUPPLEMENT

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County, Sec. 2 Twp. 29S Rge. 13 XE/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C, NW/4, NW/4

Lease Owner Sohio Petroleum Company
Lease Name Swisher Well No. 3
Office Address P.O. Box 30, Casper, WY 82602
Character of Well (Completed as Oil, Gas or Dry Hole) Oil



Locate well correctly on above
Section Plot

Date Well completed June 21, 1981
Application for plugging filed January 25, 1982
Application for plugging approved March 15, 1982
Plugging commenced June 29, 1982
Plugging completed July 7, 1982
Reason for abandonment of well or producing formation Production decline to uneconomic level.
If a producing well is abandoned, date of last production 9/21 1981

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation Arbuckle Depth to top 4730 Bottom 4748 Total Depth of Well 4774
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Middle & Lower KC	Wtr. & Oil	4154	4292	5 1/2	4772	2300
Viola	Oil	4569	4576	8-5/8	533	None
Simpson Sand	Oil	4624	4629			
Arbuckle	Oil	4734	4748			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Drilled up and pushed BP to TD (4732'). Ran 2-7/8" tubing to 3000'. Spot 50
sx. cmt. on btm. Shot csg. @ 2300'. State plugger on site. Pumped in 15 sx.
gel, 6 sx. hull, 10 sx. gel, 150 sx. cmt. (30% CaCl₂). Well plugged @ 12:45
PM, 7-7-82.

Field Foreman checked cmt. level - had dropped 138'. Contacted state plugger.
Received OK to add cmt. Filled csg. 138' to surface w/readimix. Cut csg. 5'
below ground level. Weld plate on top of surface pipe.
Well P&A 7-20-82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service

STATE OF Wyoming COUNTY OF Natrona, ss.
W.H. Ward, Sohio Petroleum Co. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

DEBRA J. WILSON - Notary Public
County of Natrona State of Wyoming
My Commission Expires Mar. 12, 1984

(Signature) W.H. Ward W.H. Ward
P.O. Box 30, Casper, WY 82602
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1982

Debra J. Wilson
Notary Public.

My commission expires 3-12-84

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1982

CONSERVATION DIVISION
Wichita, Kansas

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Swisher #3
 150' S of G-NW-NW
 Sec 2-29S-13W
 Pratt County Kansas

Commenced: 6-14-81

Completed: 6-26-81

OPERATOR: SOHIO PETROLEUM CO.

From	Depth to	Formation	Remarks
0	535	Redbed-Clay	
535	1195	Redbed-Shale	Ran 13 jts of 23# 8 5/8" csg set @ 531' Cemented w/
1195	3478	Shale	325 sks 60/40 Posmix - 2% Gel
3478	4095	Lime-Shale	3% CC - 50 sks Class A
4095	4774	Lime	3% CC PD @ 7:15 a.m. 6-15-81

4774 - TD

Ran 154 jts of 14# 5 1/2" csg set @ 4773' Cemented w/ 50 sks Halcolite + 125 sks 50/50 Posmix PD @ 10:00 a.m. 6-26-81

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 30th day of June, 1981.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

