


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-097-10024-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW&SW" or footage from lines App NW NW SW
Lease Owner Graham-Miller Oil Company
Lease Name Piester Well No. 2
Office Address 1005 East Second, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 6, 1955 19
Application for plugging filed October 6, 1955 (verbal) 19
Application for plugging approved October 6, 1955 (verbal) 19
Plugging commenced October 6, 1955 19
Plugging completed October 7, 1955 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	357'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set at 350 feet
with 20 sacks cement. Capped
with 10 sacks cement at 35
feet.

RECORDED
INDEXED
OCT 13 1955
WICHITA


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graham-Messman-Rinehart Drilling Company
Address 1005 East Second, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
1005 East Second, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of October, 19 55

My commission expires November 5, 1958 Juanita L. Lewis Notary Public.



NO. 2 PIESTER

WELL RECORD

Location: App NW NW SW, 24-298-16W
Kiowa County, Kansas

Commenced: September 25, 1955

Operator: Gramhart-Miller Oil Company
1005 East Second, Wichita, Kansas

Completed: October 6, 1955

Elevation: 1944 KB

Contractors: Graham-Messman-Rinehart Drilling Co.
1005 East Second, Wichita, Kansas

Production: D&A

Casing Records: 8 5/8" @ 357' w/250 sacks cement

.....L O G.....

Clay-Sand	359
Red Bed	480
Red Bed-Shale	839
Anhydrite	854
Shale-Shells	1930
Shale-Lime	2142
Lime-Shale	2282
Shale-Red Bed-Cyp	2498
Shale-Shells	2650
Lime-Shale	2984
Shale-Lime	3122
Lime-Shale	3300
Shale-Lime	3614
Lime-Shale	3736
Shale-Lime	4028
Lime-Shale	4158
Shale-Lime	4222
Lime	4334
Shale-Lime	4446
Lime	4490
Shale-Lime	4575
Lime-Sand	4594
Mississippi	4670 R.T.D.

Sample Tops:

Heebner 3876 (-1932)
Douglas 3929 (-1985)
Brown Lime 4043 (-2099)
Lansing 4061 (-2117)
Penn. Sd 4577 (-2633)
Mississippi 4594 (-2650)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me
this 11th day of October 1955.

Juanita L. Davis
Notary Public

My Commission Expires: November 5, 1958

PLUGGING
FBI SEC 24 729 N. 16 W
BOOK PAGE 7 LINE 15