

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

5-21-85

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15 - 151 - 21,593 ^{60 70} (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F. G. Holl OPERATORS LICENSE NO. 5056
ADDRESS 6427 East Kellogg
Wichita, Kansas 67207 PHONE # (316) 684-8481

LEASE (FARM) Hirt WELL NO. 1-30 WELL LOCATION NE NE NE COUNTY Pratt
SEC. 30 TWP. 29S RGE. 12W (~~E) (W)~~ TOTAL DEPTH 4795' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8" SET AT 267' KBCEMENTED WITH 210 SACKS
CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill hole with heavy mud plugged through
open ended drill pipe, circ before plugged, 50 sacks at 820'; 50 sacks at 280'; 1/2 sack
hulls, plug and 10 sasks at 40'. 15 sacks in rathole with joint of pipe. Use 60/40 Pozmix, 2%
(If additional space is needed use back of form) gel (total 4%) and 3% cc.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 5:00 PM, 5-16-85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: RECEIVED
STATE CORPORATION COMMISSION

Jim Shriner PHONE # (316) 378-2131 MAY 21 1985
ADDRESS P. O. Box 129
Sterling, Kansas 67579 CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR Sterling Drilling Company LICENSE NO. 5142
ADDRESS P. O. Box 129
Sterling, Kansas 67579 PHONE # (316) 278-2131
STERLING DRILLING COMPANY

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: F. A. Wuellner
(Operator or Agent)
F. A. Wuellner, Secretary
DATE: May 17, 1985