

1040990

8-18

API NUMBER 15- 151-21,471 - 00-00

STATE CORPORATION COMMISSION

Wichita State Office Bldg. PLUGGING SECTION App. SW NE SE, SEC. 1, T 28 S, R 15 W/EX  
130 S. Market, Room 2078  
Wichita, KS 67202

1450 feet from S section line  
1030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5501

Lease Name Cosby Well # 3

Operator: Raymond M. Goodin Trust

County Pratt 152.75

Name & Address 3300 Carlock

Well Total Depth 4700 feet

Wichita, KS 67204

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 9:15 a.m. Day: 18 Month: 8 Year: 19 95

Plugging proposal received from Alan Wratle

(company name) Clarke Corporation (phone) 316-886-5665

Work: 5 1/2" at 4700' w/250 sx cement. Perfs at 4466-76'

1st plug sand back to 4400' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 9:45 a.m. Day: 18 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

RECEIVED STATE CORPORATION COMMISSION

AUG 23 1995

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED (if to be observed) observe this plugging.

DATE SEP 01 1995

Signed [Signature] (TECHNICIAN)

INV. NO. 43399