

1 061095

4-13-88

98

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,476 - 00-00

NW SW SE, SEC. 1, T 28 S, R 15 W/E

1160 feet from S section line

2200 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3597

Lease Name Cosby Well # 4

Operator: Servco Production/was Robert Gay  
Name & Energy

County Pratt 151.52

Address P.O. Box 266

Well Total Depth 4662 feet

Plains, KS 67869

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2:15 p.m. Day: 13 Month: 4 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4660' Perfs at 4468-84'

1st plug sand back to 4418' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pumped 180 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3 p.m. Day: 13 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4418' and dumped 5 sx cement on top of

sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 130 sx cement.

Maximum pressure 650 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% and by Halliburton. Recovered 2141' of 5 1/2" casing.

(If additional STATE CORPORATION COMMISSION necessary, use BACK of this form.)

INVOICED

observe this plugging.

APR 19 1988

Signed Paul A. Luetke (TECHNICIAN)

DATE 4-26-88

4-19-88

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 20470