

To: 1 041270  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-151-22,019-40-00  
SW SW SW, SEC. 21, T 29 S, R 12 W XX  
330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 5056  
Operator: F.G. Holl Company, L.L.C.  
Name:  
Address P.O. Box 780167  
Wichita, KS 67278-0167

Lease Name Dauner Well / 1-21  
County Pratt 155.03  
Well Total Depth 4770 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_  
Plugging Contractor Pratt Well Service License Number 5893  
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:30 a.m. Day: 23 Month: 10 Year: 19 97  
Plugging proposal received from Ken Gates  
(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4769' w/225 sx cement, CIBP at 4327', PBD 4737', Perfs at 4288-4361'  
1st plug sand back to 4230' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Scott Alberg  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10 a.m. Day: 23 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4185' and dumped 4 sx cement on top of sand  
bridge through dump bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 700 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2700' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I (and/or XXXXXX) observe this plugging.

DATE OCT 29 1997  
INV. NO. 49371

Signed Stephen J. Pfeifer  
(TECHNICIAN)