

1 090136

10-24

239

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
290 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,966 - 06-01

SE SW SE, SEC. 20, T 29 S, R 12 W 1/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

330 feet from S section line

1650 feet from E section line

Operator: F.G. Holl Company

Lease Name Wray Well # 1-20

Name & Address P.O. Box 780167

County Pratt 154.73

Wichita, KS 67207

Well Total Depth 4761 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:15 p.m. Day: 24 Month: 10 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4735' w/175 sx cement, BPTD 4694'. Perfs at 4364-75, 4342-56'

1st plug set CIBP at 4300' and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:40 p.m. Day: 24 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4300' and dumped 4 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 150 sx cement.

Maximum pressure 650 psi and shut in 400 psi.

RECEIVED STATE CORPORATION COMMISSION

OCT 29 1991

Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3214' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did) ~~not~~ observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 11-13-91

INV. NO. 33698