

1 080363

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

100' API NUMBER 15- 151-21,206 - 00-00 *R*
NW C NW NE, SEC. 18, T 29 S, R 12 W/XX

Approx. 4720 feet from S section line
Approx. 1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6327 - 5105
Kan-Ex, Inc. sold to
Operator: Clarke Corporation
Name & Address P. O. Box 187
Medicine Lodge, KS 67104

Lease Name Brubaker Well # 1
County Pratt 149.70
Well Total Depth 4606 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 376 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 pm Day: 8 Month: April Year: 1985

Plugging proposal received from Elmo Morgenstert

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 4568' Perfs at 4447-54' 4490-93'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Orders given by Paul A. Luthi

Plugging Proposal Received by J. A. [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:50 pm Day: 8 Month: April Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 23 1985

CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 300 psi and shut in 250 psi

Remarks: Recovered 2600' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to customer) observe this plugging.

Signed J. A. [Signature]
(TECHNICIAN)

DATE 5-3-85

NV. NO. 7926