

1 080249

API NUMBER 15-151-21,507-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE SW, SEC. 18, T 29 S, R 12 W EX
1980 feet from ~~XXX~~ SE Corner of section line
3300 feet from ~~XXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Killingsworth Well # 1-18

Operator: Texas Energies, Inc.

County Pratt

Name & Address P. O. Box 947
Pratt, KS 67124

Well Total Depth 4750 154.38 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 9:00 am Day: 8 Month: November Year: 19 84

Plugging proposal received from Roger Baker

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1020' with 50 sx cement

RECEIVED

2nd plug at 390' with 50 sx cement

11-08-84 STATE CORPORATION COMMISSION

3rd plug ^{solid bridge} hulls - plug at 40' -- cement to surface with 10 sx cement

NOV 08 1984

5th plug to circulate rat hole with 10 sx cement

CONSERVATION DIVISION

6th plug to circulate mouse hole with 10 sx cement

Wichita, Kansas

Plug water well with 5 sx Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 9:45 am Day: 8 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 390' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement and plugged water well with 5 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie.

(If additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

INVOICED

Signed J. H. Metz (TECHNICIAN)

DATE 11-19-84

INV. NO. 4814