

1 080346

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SW NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,420 - 80 - 00

SW SW NE, SEC. 29, T 29 S, R 12 W/E

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Kennedy "H" Well # 1

Operator: TXO Production Corp.

County Pratt 149.50

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 4600 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 426 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 15 Month: March Year: 1985

Plugging proposal received from Bill Faulds

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 3035' PBSD 2993' Perfs at 2821-30'

1st plug sand back to 2770' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement

Plugging Proposal Received by J.A. [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:20 pm Day: 15 Month: March Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 2770' and dumped 4 sx cement on top of sand

through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement

RECEIVED STATE CORPORATION COMMISSION

MAR 25 1985 3-25-1985

Maximum pressure 600 psi and shut in 500 psi

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun Recovered 2404' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(did not observe this plugging.)

DATE 3-26-85

Signed J.A. [Signature] (TECHNICIAN)

INV. NO. 7461