

1 040827

2-21

API NUMBER 15-151-21,461-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 NE SW, SEC. 29, T 29 S, R 12 W/EX

2310 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Hearn Well # 1-29

Operator: F.G. Holl Company

County Pratt

Name & Address

Well Total Depth 4575 148.69 feet

P.O. Box 780167

Conductor Pipe: Size _____ feet

Wichita, KS 67278-0167

Surface Casing: Size 8 5/8 feet 437

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:30 p.m. Day: 21 Month: 2 Year: 1994

Plugging proposal received from Thom Pool

(company name) F.G. Holl Co. (phone) 316-995-3171

Work: 4 1/2" at 4575' w/300 sx cement, PBTD 4562', Perfs at 4356-60, 4330-35', Squeezed 2801-6
1st plug sand back to 4196' and dump 4 sx cement on top of sand bridge through bailer,

2nd plug pump 200 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx
cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1994

Plugging Proposal Received by Steve Pfeifer
DIVISION (TECHNICIAN)
ansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 21 Month: 2 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4196' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" with 200 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, and 100 sx cement.

Maximum pressure 900 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1500' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 40052

INR. NO. 40052

Signed Stephen J. Pfeifer (TECHNICIAN)