

040127

6-14-88

API NUMBER 15- 151-21,495-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 29, T 29 S, R 12 W/E

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Hirt Well # 2-29

Operator: F.G. Holl Company
Name & Address P.O. Box 780167

County Pratt 152.39

Well Total Depth 4689 feet

Wichita, KS 67278-0167

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 242.76

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 14 Month: 6 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 3023, 28" Perfs at 2832-42'

1st plug set CIBP,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 14 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2400',

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

6-22-1988 JUN 22 1988

Maximum pressure 600 psi and shut in 300 psi.

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2214' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (If desired) observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 6-29-88 INV. NO. 21123