

1040012

11-16-87 15-151-01706-00.00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 12/4/85

NE NE SE, SEC. 1, T 28 S, R 15 W/EX

2310 feet from S section line  
990470 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9069

Lease Name Cullison Well # 1

Operator: General Oil Company, Inc.  
Name & Address: 1540 North Broadway, Suite 202  
Wichita, KS 67214

County Pratt 152.43

Well Total Depth 4690 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 427

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 6:30 p.m. Day: 16 Month: 11 Year: 19 87

Plugging proposal received from Bill Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4688' 7" at 3100' PBD 4538' Perfs at 4474-94' Elevation 1958' GL

1st plug pump 1 sx hulls and 50 sx common cement to 4300',  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi & Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:15 p.m. Day: 16 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 50 lbs. hulls and 50 sx common cement,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 50-200 psi and shut in 50 psi.

Well went on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2401' of 7" casing, 3407' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

NOV 19 1987  
11-19-87  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

observe this plugging.

DATE 12-2-87

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 19027

11-16