

4-25

To: 1 040270  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,732-00-00  
SW SE NE, SEC. 1, T 28 S, R 15 W/EK  
2970 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5010

Lease Name Huitt Well # 1  
County Pratt

Operator: Knighton Oil Company, Inc.  
Name &  
Address 710 Petroleum Building  
Wichita, KS 67202

Well Total Depth 4676 feet

RECEIVED  
STATE CORPORATION COMMISSION  
5389  
MAY 3 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well  Gas Well \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:45 a.m. Day: 25 Month: 4 Year: 19 89

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4600' PBD 4600' Perfs at 4531-37, 4507-17, 4528-38'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 25 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 450 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2135' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
i (cc) to (XXX) (XXX) observe this plugging.

DATE 5-8-89

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INV. NO. 24637