

To: 1 040513
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-24
API NUMBER 15- 151-22,037-00-00
C NW NW, SEC. 36, T 28 S, R 14 W/EK
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5010

Lessee Name Beard Well # 2
County Pratt 35.00
Well Total Depth 832 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 307

Operator: Knighton Oil Company, Inc.
Name & Address 710 Petroleum Bldg.
Wichita, KS 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A X Lost hole
Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company License Number 5929
Address 310 W. Central, #117, Wichita, KS 67202

Company to plug at: Hour: 5:45 p.m. Day: 24 Month: 2 Year: 19 91

Plugging proposal received from John Armbruster
(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug pump 250 sx common cement w/3% cc at 25',
2nd plug top off hole with 5-7 sx cement,
3rd plug to circulate rathole with 15 sx cement,
4th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
2-28-91
FEB 28 1991
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None
Operations Completed: Hour: 6:30 p.m. Day: 24 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set 8 5/8" packer at 25', pumped down 8 5/8" surface
pipe through Kelly and packer with 300 sx common cement w/3% cc. Squeezed at 1500#.
2nd plug released packer and topped out 8 5/8" with 5-7 sx cement,
3rd plug to circulate rathole with 15 sx cement (60/40 Pozmix 6% gel),
4th plug to circulate mousehole with 10 sx cement (60/40 Pozmix 6% gel),
Water well plugged with 10 sx 60/40 Pozmix 6% gel.

Remarks: Cemented by Halliburton. Hole flowing approx. 1000 BPH from 832'.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 3-11-91
INV. NO. 31084
observe this plugging.

Signed Stephen J. Durrant (TECHNICIAN)