

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20221-00-00
Spot: CSENE Sec/Twnshp/Rge: 33-29S-34W
1980 feet from N Section Line, 660 feet from E Section Line
Lease/Unit Name: LESLIE Well Number: 1-33
County: HASKELL Total Vertical Depth: 5620 feet

Operator License No.: 4824 Conductor Pipe: Size _____ feet:
Op Name: PIONEER NATURAL RESOURCES USA, I Surface Casing: Size 8.625 feet: 1824 WITH 950 SX CMT
Address: 5205 N. O'CONNOR BLVD. Production: Size 4.5 feet: 5620 WITH 650 SX CMT
IRVING, TX 75039 Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/04/2002 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: SHOOT OFF AT 1200'. 40 SX PLUG AT STUB. PLUG AT 650' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/04/2002 3:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 5360'. PERFS AT 2888-2930'. CIBP @ 2940' OVER LOWER PERFS. CASING STUCK AT 1300'. PUMP 20 SX CMT & 200# HULLS OVER PERFS. LOAD HOLE WITH MUD. 1ST PLUG AT 1172' WITH 40 SX CMT. 2ND PLUG PULL TO 650' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

RECEIVED
NOV 07 2002
KCC WICHITA
11-7-2002

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1192' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

(TECHNICIAN)

INVOICED

DATE 11-7-02

INV. NO. 2003060787

Form CR-2/B