

To: 1 031409
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Mark, Room 2078
Wichita, KS 67202

API NUMBER 15-151-21,464 - 60-60
E/2 SE, SEC. 36, T. 29 S, R. 12 W
1320 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8045
Operator: Carl Dudrey
Name & Address: P.O. Box 65
St. John, KS 67576

Lease Name Dudrey Well # 3
County Pratt 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 341

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:20 a.m. Day: 6 Month: 9 Year: 19 96

Plugging proposal received from Mike Kelso
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 5 1/2" at 3899' w/300 sx cement, Perfs at 2630, 3691, 3875', Cement plug at 3000'
1st plug sand back to 2580' and dump .5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 12:10 p.m. Day: 6 Month: 9 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 2580' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and/or my agent) hereby observe this plugging.

DATE 9-20-96

Signed Steve Middleton (TECHNICIAN)

INV. NO. 46527

15151-21969-00-00

McGINNESS & McGINNESS

Consulting Geologists

1026 Union Center Bldg. 267-6065 Wichita, KS 67202

GEOLOGIST'S REPORT DRILLING TIME AND SAMPLE LOG

OPERATOR CARL DUDREY
 LEASE DUDREY WELL NO. 3
 FIELD HARDING EXT.
 LOCATION CE/2 SE
 SEC. 36 TWP. 29^S RNG. 12^W
 COUNTY PRATT STATE KANSAS

ELEVATIONS

KB 1861
 DF _____
 GL 1852

MEASUREMENTS ARE ALL
 FROM KB


CONTRACTOR DUNNE-GARDNER RIG #1
 COMM. 7-31-84 COMP. 8-8-84
 RTD. 3900 LOG TD 3903
 SAMPLES SAVED FROM 1900 TO TD
 DRILLING TIME KEPT FROM 1900 TO TD
 SAMPLES EXAMINED FROM 1900 TO TD
 GEOLOGICAL SUPERVISION FROM 1900 TO TD
 MUD UP 3380 TYPE MUD CHEMICAL
 WELL SITE GEOLOGIST D. H. McGINNESS

CASING RECORD

SURFACE _____
8 5/8" @ 341' / 325 SX
 PRODUCTION _____
5 1/2" @ 3899' / 300 SX

ELECTRICAL SURVEYS
 GEARHART
 DIL-CDL-CNL-WEL

FORMATION	LOG		SAMPLE		STRUCT. COMP.
	TOP	DATUM	TOP	DATUM	
CHASE	1974	(-113)	1973	(-112)	+9'
COUNCIL GROVE	2332	(-471)	2335	(-474)	+1'
RED EAGLE	2626	(-765)	2623	(-762)	-1'
ONAGA	2750	(-889)	2751	(-890)	+3'
INDIAN CAVE	2766	(-905)	2771	(-910)	+7'
WABAUNSEE	2799	(-938)	2803	(-942)	+4'
BURLINGAME	3097	(-1236)	3103	(-1242)	-
HOWARD	3176	(-1315)	3176	(-1315)	-
TOPEKA	3316	(-1455)	3313	(-1452)	-
ELGIN SD	3530	(-1669)	3532	(-1671)	-
HEEPNER	3690	(-1829)	3691	(-1830)	-
LANSING	3874	(-2013)	3875	(-2014)	-



REFERENCE WELL FOR STRUCTURAL COMPARISON
Dudrey #1 CSE SE 36-29^S 12^W Pratt Co., KS

RECEIVED
 CORPORATION COMMISSION
 JUL 1 11 1986
 FILED - WICHITA, KANSAS