

1 030605

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App. C NE NW, SEC. 24, T 29 S, R 16 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-20812A
4670 feet from S section line
3375 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Piester Well # 1

Operator: TXO Production Corp.
Name & Address 155 North Market, Suite 1000
Wichita, KS 67202

County Kiowa 35.00

Well Total Depth 690 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X ^{OWWO}

Other well as hereinafter indicated _____

Plugging Contractor FWA Drilling Co., Inc. License Number 6165

Address P. O. Box 970, Yukon, OK 73099

Company to plug at: Hour: 7:00 am Day: 5 Month: December Year: 19 85

Plugging proposal received from Allen Dick

(company name) TXO (phone) 316-269-7600

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 420' with 40 sx cement solid bridge
- 2nd plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 4th plug to circulate rat hole with 15 sx cement
- 5th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:00 am Day: 5 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 420' with 40 sx cement, 2nd & 3rd plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 4th plug to circulate rat hole with 15 sx cement, 5th plug to circulate mouse hole with 10 sx cement

Drilled out of old hole at 590' - still in hard cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 16 1985

INV. NO. 11538

RECEIVED
STATE CORPORATION COMMISSION
12-10-1985 Signed Steve Durrant
(TECHNICIAN)

JAN 15 1986

CONSERVATION DIVISION
Wichita Kansas