

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21925-00-00
Spot: CNWNW Sec/Twnshp/Rge: 35-30S-12W
4470 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: BALDWIN Well Number: 2-35
County: BARBER Total Vertical Depth: 4680 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Conductor Pipe: Size feet: 152.10
Surface Casing: Size 8.625 feet: 351 WITH 200 SX CMT
Production: Size 4.5 feet: 4516 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/08/2002 9:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SET CIBP @ 3935' & 2 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/08/2002 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4474'. PERFS AT 4262-72'. CASING LEAK. DEPTH OF LEAK IS UNKNOWN. TOC AT 3830'. SET CIBP @ 3935' AND PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PUMP DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT. MAXIMUM PRESSURE 650#. SHUT IN PRESSURE 500#.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 16 2002
1-16-2002
CONSERVATION DIVISION

Signed

Stephen J. Pfeifer
(TECHNICIAN)

JAN 15 2002
INVOICED
DATE Jan 17, 02
INV. NO 2002061268

Form 2/3