

1 040149

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,446-60-00

NW SW SE, SEC. 30, T 29 S, R 12 WXX

990 feet from XX/S section line

2310 feet from XX/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Kennedy Well # 3-30

Operator: F. G. Holl

County Pratt

Name & Address 6427 East Kellogg

Well Total Depth 4770 155.03 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well Gas Well Input Well SWD Well D&AX

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Co. License Number 5142

Address P. O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 3:00 pm Day: 7 Month: July Year: 19 84

Plugging proposal received from Tom Meyers

(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4700' with 50 sx cement

2nd plug at 1070' with 50 sx cement

3rd plug at 320' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10
sx cement, plug water well Plugging Proposal Received by Edgar Knobloch

with 5 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:15 pm Day: 7 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4700' with 50 sx cement, 2nd plug at 1070' with 50 sx
cement, 3rd plug at 320' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx
cement, 7th plug to circulate mouse hole with 10 sx cement, and plugged water well with
5 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton # 82487

(If additional description is necessary, use BACK of this form.)

(If did not, observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

7-11-1984

JUL 11 1984

CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 7-13-84

WIL. NO. 2469

7-7