

1 060571

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,593 -00-00

NE NE NE, SEC. 30, T 29 S, R 12 W

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Hirt Well # 1-30

Operator: F. G. Holl

County Pratt 15.5.84

Name & Address 6427 East Kellogg

Well Total Depth 4795 feet

Wichita, KS 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sterling Drilling Co. License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 5:00 pm Day: 16 Month: May Year: 19 85

Plugging proposal received from Jim Shriner

(company name) Sterling (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1897
Circulate 10 minutes Anhydrite 814-30'

1st plug at 820' with 50 sx cement

2nd plug at 280' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 pm Day: 16 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 820' with 50 sx cement, 2nd plug at 280' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

MAY 28 1985 5-28-19 85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

(Do not) observe this plugging.

INVOICED

6-6-85

Signed Paul A. Luthi (TECHNICIAN)

8368

INV. NO.