

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151 - 21,327 - 00-00

NW NE NW , Sec. 31 , T 29 S, R 12 W/EK

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Mohney Well # 1-31

Operator: Texas Energies, Inc.  
Name & P. O. Box 947  
Address Pratt, KS 67124

County Pratt

Well Total Depth 4790 feet

*\$155.67*

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstates Oilfield Services License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: \_\_\_\_\_ Day: 26 Month: September Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO \_\_\_\_\_

(company name) Wheatstates (phone) 316-672-7581

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 4700' with 50 sx cement

2nd plug at 810' with 50 sx cement

3rd plug at 390' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement, 7th plug to circulate mousehole with 10 sx cement. Plug water well with 5 sx cement Signed Steve R. Rount

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: \_\_\_\_\_ Day: 26 Month: September Year: 19 83

ACTUAL PLUGGING REPORT 1st plug at 4700' with 50 sx cement, 2nd plug at 810' with

50 sx cement, 3rd plug at 390' with 40 sx cement, 4th plug and 5th plug - solid

bridge - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 10 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Plug water well with 5 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc

I hereby certify that the above plugging instructions were given as herein stated and that I (~~saw~~ / did not) observe this plugging.

**INVOICED**  
DATE 3-2-84  
INV. NO. 0478

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 29 1984  
CONSERVATION DIVISION  
Wichita, Kansas  
*02-29-84*

Signed Steve R. Rount  
(TECHNICIAN)