

1 090137

10-2K

233

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,980 -00-00

W/2 NW SW, SEC. 31, T 29 S, R 12 WXR

1980 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Carver Well # 1-31

Operator: F.G. Holl Company
Name &

County Pratt 155.41

Address P.O. Box 780167
Wichita, KS 67207

Well Total Depth 4782 feet

Conductor Pipe: Size feet

Surface Casing: Size 13 3/8 feet 333

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 24 Month: 10 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4782' w/225 sx cement, Perfs at 4417-20'

1st plug set CIBP at 4370' and dump 4 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 225 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:40 a.m. Day: 24 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4370' and dumped 4 sx cement on top,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 225 sx cement.

Maximum pressure 650 psi and shut in 300 psi.

RECEIVED STATE CORPORATION COMMISSION

OCT 29 1991

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3195' of 4 1/2" casing.

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 11-13-91

Signed [Signature] (TECHNICIAN)

INV. NO. 33699