

To: 1 010063  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,267-0000 <sup>9</sup> R

C SW NE       , SEC. 34, T 29 S, R 16 W/E  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5354  
Operator: Southern States Oil Co.  
Name & Address: Now Lasmo Energy  
P. O. Box 1365  
Great Bend, KS 67530

Lease Name Dannehohm Well # 1  
County Kiowa 150.80  
Well Total Depth 4640 feet  
Conductor Pipe: Size        feet  
Surface Casing: Size 8 5/8 feet 288

Abandoned Oil Well  Gas Well  Input Well  SHD Well  D&A

Other well as hereinafter indicated       

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:25 am Day: 31 Month: December Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4625' Open Hole  
1st plug pump 1 sack hulls and 30 sx cement to bottom  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:00 pm Day: 31 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 30 sx cement to bottom, 2nd plug  
squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released  
8 5/8" rubber plug and pumped 125. sx cement.

Maximum pressure 600 psi and shut in 500 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3366' 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE JAN 14 1986

INV. NO. 12011 12-31

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1986

FEB 5 1986  
CONSERVATION DIVISION

Signed Jacqueline L. Lutz (TECHNICIAN)

1-13-1986