

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

11-15-89

API NUMBER 15-007-21,384-6000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR TXO PRODUCTION CORP. OPERATOR'S LICENSE NO. 5171 *4/20*

ADDRESS 1660 Lincoln St., Suite 1800 *Denver, CO 80204* PHONE # (303) 861-4246

LEASE ~~(FARM)~~ Mott "B" WELL NO. 1 WELL LOCATION 1650' FWL <sup>560' FSL &</sup> COUNTY Barber

SEC. 12 TWP. 31S RGE. 12 ~~(EXX)~~(W) TOTAL DEPTH 4396' PLUG BACK TD 3960'

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. D-21,186  
CD-88235

SURFACE CASING SIZE 8-5/8" SET AT 368' CEMENTED WITH 320 SACKS

CASING SIZE 4 1/2" SET AT 4002' CEMENTED WITH 250 SACKS

PERFORATED AT 3376-8' 4 jspf, Elgin SQZD, cmt retainer @ 3370', 3351-8' 2 jspf  
Elgin SQZD, 3860-75' 4 jspf L-KC.

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill csg to +3750' w/ sand. Dump bail 4 sx cmt.

Recover +2500 4 1/2" csg. Plug 8-5/8" w/ 5 sx hulls, 30 sx 60/40 poz-mix,

1 sx hulls, .75 sx 60/40 poz-mix w/ 6% gel. Cut off & cap 8-5/8".

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED? yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be coordinated between TXO & KCC  
Field Offices.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leamon Roberson PHONE # (316) 886-5606

ADDRESS P.O. Box 125B Medicine Lodge, Kansas 67104

PLUGGING CONTRACTOR Clarke Corporation LICENSE NO. 5105

ADDRESS 107 W. Fowler Box 187, Medicine PHONE # (316) 886-1007  
Lodge, Kansas

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Cory West  
(Operator or Agent) Cory West

DATE: 11/9/89

RECEIVED 6/90  
STATE CORPORATION COMMISSION  
15 1989  
CONSERVATION DIVISION  
Wichita, Kansas

①



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

EXPIRES

15-007-21384-0000

November 16, 1989

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

TXO Production Corp.
1600 Lincoln St., Suite 1800
Denver, Co 80264

Mott "B" 1
560'FSL-3630'FEL
Sec. 12-31-12W
Barber County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760