

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19393-00-01

Spot: NESENW

Sec/Twnshp/Rge: 26-31S-5E

3740 feet from S Section Line, 3006 feet from E Section Line

Lease Name: SHANNON UNIT

Well #: 1B

County: COWLEY

Total Vertical Depth: 2338 feet

Operator License No.: 4419

Op Name: BEAR PETROLEUM, LLC

Address: PO BOX 438

HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2334		75 SX
SURF	8.625	207		125 SX

Well Type: EOR

UIC Docket No: E09056.1

Date/Time to Plug: 04/10/2015 8:00 AM

Plug Co. License No.: 3004

Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC

Proposal Revd. from: JOE BURNETT

Company: BEAR PETROLEUM, INC.

Phone: (316) 525-1225

Proposed
Plugging
Method:

AS PER KCC RULES & REGS/ CIBP @ 2329 W/ 5 SXS PERF & CIRC 260'-0'.

Plugging Proposal Received By: DAN FOX

WitnessType: PARTIAL

Date/Time Plugging Completed: 04/10/2015 6:30 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2285', DUMP BAILED 4 SXS CEMENT ON TOP OF CIBP. RIH W/ TBG @ 260', GRESSEL ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 6:30 PM 4-10-2015. GRESSEL CEMENT TICKET #43503.

Perfs:

Top	Bot	Thru	Comments
2334	2369	OH	

Remarks: COMPLIANCE/ FAILED MIT/ BACKSIDE HAS CEMENT FROM 900'-0'.

Plugged through: TBG

MAY 27 2015 *CKM*

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 14 2015

CONSERVATION DIVISION
WICHITA, KS

CC:UIC