

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20625-00-00
Spot: SESWNESW Sec/Twnshp/Rge: 23-4S-21W
1375 feet from S Section Line, 1930 feet from W Section Line
Lease Name: VEH Well #: 1
County: NORTON Total Vertical Depth: 3635 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3599		550 SX
SURF	8.625	218		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2015 1:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DAN WINDHOLZ Company: BLACK DIAMOND OIL INC. Phone: (785) 759-8403

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls and 7 sx gel.
Production perforations: 3498' - 3501'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2015 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing and pumped 50 sx cement w/200 # hulls. Pumped 7 sx gel spacer followed by 130 sx cement w/200 # hulls. Maximum pressure 700 psi. Shut in pressure 300 psi. Visually checked 8 5/8" x 4 1/2" annulus and cement was to surface.

GPS: 39.68688N -099.65869W

Perfs:

Top	Bot	Thru	Comments
3498	3501		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1242

Plugged through: CSG

MAY 27 2015 *CPM*

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CPM

MAY 13 2015