

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23575-00-00
Spot: NENWNWSW Sec/Twnshp/Rge: 31-7S-20W
2470 feet from S Section Line, 630 feet from W Section Line
Lease Name: TERESA Well #: 1
County: ROOKS Total Vertical Depth: 3570 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3568		470 SX
SURF	8.625	220		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/30/2015 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 265 sx 60/40 pozmix 4% gel cement, 400 # hulls and 12 sx gel.
Ordered another 100 sx 60/40 pozmix 4% gel cement.
Production perforations: 3348' - 3358'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2015 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement w/200 # hulls followed by 12 sx gel.
Pumped 210 sx cement w/200 # hulls. Pressure to 300 psi and then went on vacuum. Ran out of cement.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Pressured up to 150 psi. Shut in pressure 150 psi. Topped off 5 1/2" casing with 80 sx cement.

GPS: 39.40098N -099.60017W

Perfs:

Top	Bot	Thru	Comments
3358			
3348			

Remarks: QUALITY OILWELL CEMENTING TICKET # 1159

Plugged through: CSG

MAY 27 2015 *gem*

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

MAY 13 2015