

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22335-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 1-35S-2E
1475 feet from S Section Line, 330 feet from W Section Line
Lease Name: WENTWORTH Well #: 10
County: SUMNER Total Vertical Depth: 2060 feet

Operator License No.: 30253
Op Name: CYCLONE PETROLEUM, INCORPORAT
Address: 1030 W. MAIN
JENKS, OK 74037

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	1650		
PROD	4.5	1664		125 SX
SURF	8.625	250		189 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/17/2015 10:00 AM
Plug Co. License No.: 33556 Plug Co. Name: DRAKE EXPLORATION, LLC
Proposal Rcvd. from: DARREN BROYLES Company: DRAKE EXPLORATION, LLC. Phone: (620) 986-5583

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 03/17/2015 6:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

WIRELINE COMPANY SET CIBP @ 1480' PERFORATE 10 SHOTS @ 300'-302'.
CIRCUALTED 5 BBLs OF FRESH WATER THEN PUMPED IN 90 SX OF 60/40 POS. MIX
WITH 4% GEL. CIRCUALTED TO SURFACE, CASING STANDS FULL. PLUG JOB
COMPLETE. ELITE CEMENTING, LLC. NO TICKET INFORMATION AVAILABLE.

Perfs:

Top	Bot	Thru	Comments
1564	1572	CSG	
1536	1572		

Remarks: GAS WELL HAS NOT PRODUCED FOR OVER 10 YEARS.

Plugged through: CSG

MAY 27 2015 *ckm*

District: 02

Signed _____

Daniel R. Fox
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAY 14 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS