

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23137-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 20-8S-18W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: PITTMAN A Well #: 1
County: ROOKS Total Vertical Depth: 3468 feet

Operator License No.: 33476
Op Name: DISCOVERY NATURAL RESOURCES L
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3457		150 SX
SURF	8.625	220		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2015 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ED ABERCROMBIE Company: DISCOVERY NATURAL RESOURC Phone: (620) 793-2816

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Perforated at 1470' CWC w/300 sx cement. CIBP at 3250'. Production perforations: 3391' - 3468'.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2015 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3250' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2151 and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1037' and pumped 130 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/20 sx cement. Visually checked 8 5/8" x 4 1/2" annulus. Cement to surface.

GPS: 39.34943N -099.35188W

Perfs:

Top	Bot	Thru	Comments
3457	3468		
3413	3416		
3391	3395		
1470	1470		

Remarks: ALLIED CEMENTING TICKET # 55762

Plugged through: TBG

MAY 27 2015 *ckm*

District: 04

Signed Pat Bedore
(TECHNICIAN) *ckm*

MAY 13 2015