

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23195-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 20-8S-18W  
330 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: PITTMAN A Well #: 2  
County: ROOKS Total Vertical Depth: 3459 feet

Operator License No.: 33476  
Op Name: DISCOVERY NATURAL RESOURCES L  
Address: 410 17TH ST STE 900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3455		150 SX
SURF	8.625	253		375 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2015 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: ED ABERCROMBIE Company: DISCOVERY NATURAL RESOURC Phone: (620) 793-2816

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/800 # hulls.  
Perforated at 1470'. CWC w/375 sx cement  
CIBP at 3350'

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2015 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3341' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2245' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1167' and pumped 90 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/25 sx cement. Visually checked 8 5/8" x 4 1/2" annulus, cement to surface.  
GPS: 39.34946N -099.35658W

Perfs:

Top	Bot	Thru	Comments
3455	3459		
3454	3459		

Remarks: ALLIED CEMENTING TICKET # 55763

Plugged through: TBG

MAY 27 2015 *ckm*

District: 04

Signed Pat Bedore  
(TECHNICIAN) *CM*

MAY 13 2015