

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-19114-00-01
Spot: SESENW Sec/Twnshp/Rge: 14-10S-21W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: DRISCOLL Well #: 2
County: GRAHAM Total Vertical Depth: 3775 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3771		150 SX
SURF	8.625	190		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/06/2015 2:30 PM
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE, LLC
Proposal Rcvd. from: RANDY WEIGEL Company: EMPIRE ENERGY E & P Phone: (785) 737-3736

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Shot perforations at 915'.
Tubing stuck in hole. Can not get out at 1516'.
Perforations at 3769' to open hole.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2015 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1485' and pumped 200 sx cement. Pulled tubing out. Tied on to casing and squeezed with 200 sx cement and 150 # hulls. Tied on to backside and squeezed with 50 sx cement. Topped off casing with 20 sx cement.
GPS: 39.18465 -099.63435

Perfs:

Remarks: QUALITY CEMENT TICKET # 1245

Plugged through: TBG

MAY 27 2015 *CKM*

District: 04

Signed *Marvin Mills*
(TECHNICIAN) *CM*

MAY 08 2015