

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21400-00-00
Spot: SWSWSENE Sec/Twnshp/Rge: 7-9S-27W
2375 feet from N Section Line, 1040 feet from E Section Line
Lease Name: HAFFNER Well #: 1-7
County: SHERIDAN Total Vertical Depth: 4425 feet

Operator License No.: 32593
Op Name: HAFFNER, DAN
Address: RR 2 BOX 49
HOXIE, KS 67740

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	214		200 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/09/2015 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo-seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: NONE
Date/Time Plugging Completed: 05/09/2015 4:30 AM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @2320 w/50 sx
2nd plug @1450 w/100 sx
3rd plug @270 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:


Remarks: GLOBAL

Plugged through: DP

MAY 27 2015 *ckm*

District: 04

Signed _____



(TECHNICIAN)

CM

MAY 12 2015