

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26226-00-00
Spot: SESENW Sec/Twnshp/Rge: 26-13S-20W
2310 feet from N Section Line, 2970 feet from E Section Line
Lease Name: YOUNGER C Well #: 1
County: ELLIS Total Vertical Depth: 3890 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3874		170 SX
SURF	8.625	263		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2015 9:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DAVE FUNK Company: JASON OIL Phone: (785) 445-2025

Proposed
Plugging
Method:

Ordered 330 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2015 10:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked to casing and pumped 50 sx cement w/300 # hulls, followed by 13 sx gel, followed by 205 sx cement w/200 # hulls. Pressured to 500 psi. Shut in pressure 400 psi. Well had a Port Collar set at 1548' that was cemented on 01/03/2011 by Quality Cementing ticket # 994. Cement circulated. Dug out braden head and found cement in casing head.

GPS: 38.89330 -099.51329

Perfs:

Top	Bot	Thru	Comments
3827	3830		
3780	3783		
3680	3684		
3640	3644		
3562	3566		
3514	3520		

Remarks: QUALITY CEMENTING TICKET # 1241

Plugged through: CSG

MAY 27 2015 *CKM*

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

MAY 06 2015