

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-003-01855-00-01
Spot: NWSWNE Sec/Twnshp/Rge: 4-21S-21E
4897 feet from S Section Line, 2149 feet from E Section Line
Lease Name: NORTH UNIT Well #: O 10
County: ANDERSON Total Vertical Depth: 765 feet

Operator License No.: 33663
Op Name: KING OIL, INC.
Address: 27224 NE UTAH RD
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	756		69 SX
SURF	6.25	20		7 SX

Well Type: EOR UIC Docket No: E01862.2 Date/Time to Plug: 04/23/2015 1:00 PM
Plug Co. License No.: 33663 Plug Co. Name: KING OIL, INC.
Proposal Rcvd. from: RICKY L. KING Company: Phone: (785) 448-5934

Proposed Plugging Method: run 1 inch pipe in to 750feet pump in 10 sacks of 50% portland and 50%flyash pull pipe to a depth of 400feet pump in 10 sacks of portland and flyash, pull 1 inch pipe to 150feet from surface and filled to top with cement and flyash/

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 04/23/2015 2:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:
50 FOOT CEMENT PLUG AT TD (750 FEET), 50 FOOT PLUG AT K.C. (400 FEET), CEMENT 150 FEET TO SURFACE WITH GEL SPACERS BETWEEN CEMENT PLUGS. A TOTAL OF 55 SACKS OF CEMENT WERE USED TO PLUG WELL.

Perfs:

RECEIVED
KCC DIST # 3
MAY 20 2015
CHANUTE, KS

LS

Remarks: FAILED MIT.
Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION
MAY 26 2015
CONSERVATION DIVISION
WICHITA, KS

MAY 27 2015 *ckm*

District: 03 Signed *Levi Short*
(TECHNICIAN)

alc