

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

10-11-86

API NUMBER 15-129-20,823-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549
ADDRESS P.O. Box 351, Liberal, Kansas 67901 PHONE # (316) 624-6253
1980 FWL &
LEASE (FARM) CENTRAL LIFE "A" WELL NO. 1 WELL LOCATION 660 FSL COUNTY Morton
SEC. 34 TWP. 34S RGE. 42 ~~(E)~~ or (W) TOTAL DEPTH 4900' PLUG BACK TD surface

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8-5/8" SET AT 1320' CEMENTED WITH 625 SACKS
CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plugs spotted thru DP; 50 sxs @ 4700', 50 sxs @ 2500', 50 sxs @ 1350', 40 sxs @ 600'. A wooden wiper plug pushed to 40' w/ 10 sxs 40'-0' and 15 sxs circ. in rathole. Cement type: 60/40 Poz w/ 6% gel. Spot heavy drilling mud between plugs.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 9/10/86 2100hrs

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jim Barlow

PHONE # (316) 624-6253

ADDRESS P.O. Box 351, Liberal, Kansas 67901

PLUGGING CONTRACTOR Halliburton Services

LICENSE NO. _____

ADDRESS P.O. Box 1598, Liberal, Kansas 67901

PHONE # (316) 624-3879

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: _____

M. L. Pease
(Operator or Agent)

M. L. Pease, Division Production Engineer

DATE: October 10, 1986

OCT 14 1986

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS