

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

10-13-89

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 15-129-10554-0000 NA (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549 8/90

ADDRESS P. O. Box 351, Liberal, KS 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Riley WELL NO. 4-27 WELL LOCATION C NW SE COUNTY Morton

SEC. 27 TWP. 34S RGE. 42 (E) or (W) TOTAL DEPTH 4590 PLUG BACK TD 4582

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1498' CEMENTED WITH 800 SACKS

CASING SIZE 5 1/2" SET AT 4624' CEMENTED WITH 300 SACKS

PERFORATED AT 4564-4576 Basal Morrow

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1) Set CIBP @ 4500 & dump 2 sxs cement on top. (2) Circulate hole with 36 Vis mud. (3) Rig up casing pullers, locate free-point and cut-off casing. (4) Spot 25 sxs cement plug @ cut-off. (5) Start pulling casing. (over)

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No* IS ACO-1 FILED? No*
(If not explain.) Well Record and Logs already on file.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon KCC approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Marvin B. Johnson PHONE # (316) 697-2186

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargent's Casing Pullers LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: M. L. Pease
(Operator or Agent) M. L. Pease

DATE: 10/11/89

Division Production Manager

①

(6) Spot 25 sxs cement plug in and out of surface casing shoe. (7) Spot 25 sxs cement plug @ 50'. (8) Cut-off casing 3' below ground level and weld-on cap. (9) Restore location.



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
JAN 16 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

October 16, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Anadarko Petroleum Corporation
P.O. Box 351
Liberal, KS 67905-0351

Riley 4-27
C NW SE
Sec. 27-34-42W
Morton County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of Shari Feist Albrecht.

Shari Feist Albrecht
Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760