


WELL PLUGGING RECORD 2-7-62

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Morton County. Sec. 30 Twp. 34 Rge. (E) 42 (W)
Location as "NE/CNW%SW%" or footage from lines G SW
Lease Owner Anadarko Production Company
Lease Name Pence "A" Well No. 1
Office Address P. O. Box 351, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 28 1962
Application for plugging filed January 29 1962
Application for plugging approved January 30 1962
Plugging commenced February 2 1962
Plugging completed February 3 1962
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	591	
				4 1/2	3099	2429

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 2935' to 2850'. Spotted 5 sacks cement. Shot off & pulled 4-1/2" casing at 2429. Mudded hole to 575'. Spotted 20 sacks cement. Mudded hole to 40' and 10' Rock Bridge. Spotted with 10 sacks cement.

FEB 7 1962
CONSERVATION DIVISION
Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Crews
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF MORTON, ss.
R. L. O'Shields (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. O'Shields
R. L. O'Shields, Vice President
P. O. Box 351, Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of February, 1962
Howard L. Vanpiper
Notary Public.

My commission expires _____

10
DRILLER'S LOG

WELL NAME Pence "A" No. 1 COMPANY OPERATING Anadarko Production Company
 ADDRESS of COMPANY Box 351, Liberal, Kansas

WELL LOCATION C 1/2 SW 1/2,
1320 ft. North of South line,
1300 ft. East of West line; Sec. 30 Twp. 34 Rge. 42, Morton County, Kansas

DRILLING STARTED January 4, 1962, DRILLING COMPLETED January 13, 1962
 WELL COMPLETED January 3, 1962 WELL CONNECTED _____, 19

ELEVATION 3525 ft. Ground Level CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8	591	370	
4 1/2	3099	150	2429

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Clay	0	245			
Red Bed & Sand	245	725			
Red Bed & Gypsum	725	1185			
Red Bed & Sand Gypsum Streaks	1185	1435			
Shale & Shells	1435	1900			
Shale, Shells & Sand	1900	2185			
Shale	2185	2348			
Lime & Shale	2348	3100			
Total Depth	3105				

FEB 7 1962
 STATE CORP. REG. DIVISION
 CONSERVATION DIVISION
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: Well has been plugged and abandoned.